

## Proposals Due 4:00 PM Thursday 12 July 2018

9 July 2018

TO: RFP 18-076C Interested Firms

SUBJECT: Amendment No. 3 to Request for Proposal (RFP) 18-076C  
For Stairway Egress and Safety improvements Project

### **The following additions/changes are hereby incorporated into the RFP:**

The due date for receipt of proposals is extended to 4:00 PM, Thursday, 12 July 2018.

### **Answers to Questions Received:**

1. Drawing ED.1 Detail 5 Note 1 is calling to remove Romex feed from existing starters. During the site visit no Romex wire was observed entering the trough. Please advise.

The Romex feed is visible on the first floor of Stair F. See 4/ED.1, note 5. Craig Shaw of PPPL informed EwingCole (EC) that the Romex connected to the motor starters P1 and P2 in Mech Room 104. Neither PPPL nor EC opened the existing panels or trough to confirm that Romex was continuous from the point where it is visible to the point documented in detail 5/ED.1. The contractor is responsible for tracing out all power wiring per the stair tower general notes on ED.1.

2. Drawing EP.1 Detail # 6 Note # 1- What is the wire size and OCP of the existing feed.

Regards,

When tracing out all power wiring per the stair tower general notes on ED.1, the contractor shall field verify the existing wire size and OCP. The motor starters for pumps P1 and P2 shall be connected to the existing feeder from substation #1 as indicated.

**Please acknowledge your receipt of this RFP Amendment No. 3 by signing below and returning it with your proposal package.**

Sincerely,

Chi Man Cheung  
Procurement Specialist

TO: RFP 18-076C Interested Firms  
SUBJECT: Amendment No. 3 to RFP  
18-076C

29 June 2018  
Page 2 of 2

---

Company: \_\_\_\_\_

Signature: \_\_\_\_\_

Name: \_\_\_\_\_

Title: \_\_\_\_\_

Date: \_\_\_\_\_